

## Thessaloniki METRO



Employer : ATTIKO METRO

Construction J/V : SALINI IMPREGILO-AEGEK S.A.

Cost Estimation : 2 billion EUR

Status of Project : Under Construction

Project Description :

- o 13 Underground Stations (3 or 4 levels) and Depot
- o Fully automatic driverless operation
- o 9.6km underground line with two tracks
- o Middle distance between Stations : 700m
- o Two ventilation shafts for each station
- o Length of platform : 60m
- o Platform fully separated from track with PSD doors
- o Depot with stabling, maintenance and repair workshop facilities
- o Main Operational Control Center (OCC)

Services provided : Final Architectural Design and Detail Architectural Design for the Construction and Operation of the METRO LINE.

## Thessaloniki METRO



## Thessaloniki METRO

